

## **GENERAL NOTES**

- COORDINATE WORK WITH ALL OTHER TRADES ON SITE.
- FIELD VERIFY EXISTING CONDITIONS PRIOR TO COMMENCING WORK.
- COORDINATE ANY UTILITY SHUT-DOWNS WITH OWNER, UTILITY COMPANY AND GENERAL CONTRACTOR.

## **KEYED NOTES**

- 1) NATURAL GAS LINE STUBBED OUT OF WALL FROM FURNACE CLOSET TO REMAIN FOR ROUTING UP TO ROOF. REMOVE EXPOSED GAS LINE RUNNING ALONG BOTTOM EDGE OF EXTERIOR WALL. CAP GAS LINE STUBBED UP THRU CONCRETE SIDEWALK.
- 2 EXISTING NATURAL GAS LINE BELOW GRADE TO REMAIN.
- 3 REMOVE BELOW GRADE NATURAL GAS LINE THAT WILL BE UNDER NEW ADDITION FOOTPRINT.
- 4 EXISTING NATURAL GAS LINE UP FROM BELOW GRADE AND INTO BUILDING
- 5 REMOVE NATURAL GAS LINE BELOW GRADE TO POINT 5'-0" BEYOND NEW ADDITION FOOTPRINT.
- 6 SITE CONTRACTOR TO REMOVE BELOW GRADE SANITARY SEWER LINE FOR INSTALLING NEW PIPING.
- 7 COORDINATE WITH SITE CONTRACTOR FOR REMOVING BELOW GRADE SANITARY SEWER TO THIS POINT FOR REROUTING SERVICE. FIELD VERIFY LOCATION.
- 8 SITE CONTRACTOR TO REMOVE BELOW GRADE WATER SERVICE TO THIS POINT FOR REROUTING SERVICE. FIELD VERIFY LOCATION.
- 9 COORDINATE WITH SITE CONTRACTOR FOR REMOVING SANITARY SEWER BACKWATER VALVE ASSEMBLY.
- 10 NATURAL GAS LINE STUBBED OUT OF WALL FROM FURNACE CLOSET TO REMAIN FOR ROUTING UP TO ROOF. REMOVE EXPOSED GAS LINE RUNNING ALONG BOTTOM EDGE OF EXTERIOR WALL AND GAS LINE BELOW GRADE TO MAIN. COORDINATE WITH SITE CONTRACTOR.



the Abla Griffin Partnership L.L.C.

> 201 N. BROADWAY **SUITE 210** MOORE, OK. 73160 405.735.3477 AGP@theAGP.net www.theAGP.net

CEDAR CREEK

KFC ENGINEERING

STRUCTURAL

SALAS O'BRIEN MECHANICAL / ELECTRICAL



checked by

JULY 2023

MOORE PUBLIC SCHOOLS **BOARD OF EDUCATION** MOORE, OKLAHOMA



**CLASSROOM ADDITION** HIGHLAND WEST JUNIOR HIGH SCHOOL

PD101

CONSENT OF AGP.



Salas O'Brien Project Number: 2023-02792-00