

**CONSTRUCTION BULLETIN # 02**

Client: Abla Griffin Partnership  
Project Name: Kelley Elementary Saferoom Addition  
Project Number: 2022-04164-00

December 19, 2022

Requested by:  Owner  
 Contractor:  
 Salas O'Brien:



To: Mike Abla, Clay Griffin, AGP

This Construction Bulletin is issued to:

- Offer additional information for clarification or supplemental drawings for layout assistance.
- Request cost and time impact to initiate a change to the Contract Documents. Owner approval is required, do not commence with revisions unless directed in writing. Avoid Work in areas that may be affected by proposed change until approved or rejected. Once approved, forward Change Order documentation as required by the Contract Documents.
- Direct a required change in the Contract Documents. Proceed with change(s) as indicated. Forward Change Order documentation as required by the Contract Documents.
- Response to RFI \_\_\_\_\_.

Item No.	Description	Attachment
1	Changes to Spec 23-3300 Air Duct Accessories section 2.9 :  2.9 LOUVERS A . Manufacturers: 1) Rusk: <a href="http://www.ruskin.com">www.ruskin.com</a> . 2) Greenheck: <a href="http://www.greenheck.com">www.greenheck.com</a> . 3) United Enertech: <a href="http://www.unitedenertech.com">www.unitedenertech.com</a>	No



Item No.	Description	Attachment
	<p>4) Pottorff: <a href="http://www.pottorff.com">www.pottorff.com</a></p> <p>B . No substitutions allowed.</p> <p>C . Louver shall be UL listed as tested for FEMA saferoom and bear the AMCA certified rating for both air performance and water penetration. Adhering to ICC 500 – 2014 standards of testing, including but not limited to, both the minimum and maximum louver sizes for the debris testing as specified in chapter 8 of the ICC 500 -2014 Standard for the Design and Construction of Storm Shelters. The Mechanical Contractor shall request and present as part of the submittal package proof of UL listing and compliance to testing for ICC 500 – 2014 requirements from the manufacturer. On the possibility another louver manufacturer meets this requirement at the time of submittal substitution can be considered given proof of compliance and UL listing testing of ICC 500 - 2014.</p> <p>D . Finish to be anodized or Kynar 500 in a custom color to be selected by the Architect. Furnish sufficient paint in the same color as the louver to paint the outer surface or panels over unused portions of louvers and to paint the interior portion of ductwork visible through the louvers.</p>	

**END OF CB-02**

