



- DEMOLITION NOTES:
- 1.  INDICATES EXISTING WALLS TO BE DEMOLISH TO LIMITS INDICATED. RE: A1018 FOR LOCATIONS
 - 2. REMOVE EXISTING HOLLOW METAL DOOR & FRAME AND EXISTING WALL SYSTEM. PREPARE OPENING TO RECEIVE NEW WALL IN-FILL AND NEW H.M. DOOR FRAME
 - 3. REMOVE EXISTING HOLLOW METAL DOOR & FRAME AND PREPARE OPENING TO RECEIVE NEW WALL IN-FILL
 - 4. REMOVE EXISTING TEMPORARY WALL SYSTEM AND PREPARE OPENING TO RECEIVE NEW STOREFRONT
 - 5. REMOVE EXISTING SOFFIT SYSTEM AND ASSOCIATED FRAMING AS REQUIRED FOR NEW FRAMING AND PREFINISHED METAL SOFFIT PANEL
 - 6. REMOVE EXISTING "NO PARKING" SIGN & REINSTALL AFTER EXTERIOR WORK IS COMPLETE
 - 7. REMOVE EXISTING SLAB AT NEW DOOR LOCATIONS RE: A1008 & A1009. PREPARE AREA TO RECEIVE NEW CONCRETE SLAB AND STOOP. RE: 3A303

DEMOLITION FLOOR PLAN

3/32" = 1'-0"



GENERAL NOTES:

1. CONTRACTOR TO VISIT SITE PRIOR TO PREPARING BID & VERIFY ALL ITEMS TO BE DEMOLISHED. ANY ADDITIONAL ITEMS REQUIRING DEMOLITION THAT ARE NOT PROVIDED TO THESE DOCUMENTS SHOULD BE BROUGHT TO THE ARCHITECT'S ATTENTION OF THE ARCHITECT AND INCLUDED IN THE BASE BID.
2. ALL SALVAGEABLE ITEMS TO REMAIN OWNERS PROPERTY & SHALL BE STORED OR DISPOSED OF AS PER OWNERS INSTRUCTIONS.
3. CONSTRUCTION SHALL MEET ALL APPLICABLE CODES, ORDINANCES, REGULATIONS & STANDARDS REQUIRED BY THE CITY OF MOORE, OKLAHOMA.
4. PROTECT EXISTING STRUCTURE TO REMAIN AS REQUIRED. PROTECT EXISTING CMU WALL TO REMAIN AS REQUIRED. PROTECT EXISTING EXTERIOR WALL TO REMAIN.

