

DEMOLITION SITE PLAN




1" = 30'-0"

GENERAL NOTES:

- CONTRACTOR TO VISIT SITE PRIOR TO PREPARING BID & VERIFY ALL ITEMS TO BE DEMOLISHED. ANY ADDITIONAL ITEMS REQUIRING DEMOLITION THAT ARE NOT INCLUDED IN THESE DOCUMENTS SHOULD BE BROUGHT TO THE IMMEDIATE ATTENTION OF THE ARCHITECT AND INCLUDED IN THE BASE BID.
- ALL SALVAGEABLE ITEMS TO REMAIN OWNERS PROPERTY & SHALL BE STORED OR DISPOSED OF AS PER OWNERS INSTRUCTIONS.
- CONSTRUCTION SHALL MEET ALL APPLICABLE CODES, ORDINANCES, REGULATIONS & STANDARDS REQUIRED BY THE CITY OF MOORE, OKLAHOMA.
- PROTECT EXISTING STRUCTURE TO REMAIN AS REQUIRED.

DEMOLITION NOTES:

- DEMOLISH / REMOVE TOTAL THICKNESS OF ASPHALT W/IN BOUNDARIES INDICATED. PREPARE EXISTING SUBGRADE TO RECEIVE NEW POURED-IN-PLACE RUBBER PLAYGROUND SURFACE.
- DEMOLISH EXISTING CONCRETE CURB & GUTTER AROUND EXISTING FIRE HYDRANT TO BE RELOCATED. RE: CIVIL.
- DEMOLISH / REMOVE TOP 2" OF ASPHALT WEARING COURSE W/IN LIMITS INDICATED & REPAIR / PREPARE EXISTING ASPHALT BASE COURSE TO REMAIN TO RECEIVE NEW 2" WEARING COURSE.
- DEMOLISH / REMOVE EXISTING LIGHT POLE & CONCRETE BASE. LOCATE EXISTING ELECTRICAL CONDUIT & PROVIDE ALL MATERIALS REQUIRED FOR REMAINING LIGHT POLES TO WORKING ORDER.
- DEMOLISH / REMOVE TOTAL THICKNESS OF ASPHALT W/IN BOUNDARIES INDICATED. PREPARE EXISTING SUBGRADE TO RECEIVE NEW GENERATOR BUILDING.
- REMOVE EXISTING SUBGRADE AND PREPARE AREA TO RECEIVE NEW ASPHALT PAVING. MATCH EXISTING THICKNESS. PROVIDE NEW CURB & GUTTER AS REQUIRED. MATCH EXISTING.
- DEMOLISH / REMOVE TOTAL THICKNESS OF ASPHALT W/IN BOUNDARIES INDICATED FOR NEW GREASE INTERCEPTOR AND ASSOCIATED PIPING. RE: PLUMBING.
- DEMOLISH / REMOVE EXISTING SIDEWALK TO LIMITS INDICATED. PREPARE SUBSTRATE FOR NEW RAMPS & SIDEWALK.



ENTIRE SHEET