FIRST FLOOR

DESCRIPTION	RM. NO.	FLOOR						BASE						CEILING				CLG. HT.	REMARKS	WALLS	PAINT / COLOR SCHEDULE				
		LUXURY VINYL TILE	CARPET TILE	CERAMIC TILE	QUARRY TILE	STAINED CONCRETE	EXPOSED CONCRETE W/ HARDENER	CERAMIC TILE	RUBBER	WOOD	QUARRY TILE	NONE		2 X 2 ACOUT. LAY-IN (TEG)	GYP. BOARD	EXPOSED STRUCTURE	KITCHEN ZONE LAY-IN			CERAMIC TILE / CONCRETE MASONRY UNIT / GYP. BD. / WAINSCOT / STAINLESS STL.	CLG.	N	E	S	W	REMARKS
VESTIBULE	101	○								●				○	●			10'-8" / 11'-4"			(1)(21)	(2)(3)	(2)(3)	(2)(3)	(10)(25)
RECEPTION	102		○							●				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(3)(8)(24)
PRINCIPAL	103		○							●					●			9'-4"	EPOXY PAINT		(1)(21)	(2)	(2)	(2)	(3)(8)
TOILET	104			○				○							●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(14)(15) BASE
TESTING	105		○							●					●			9'-4"	EPOXY PAINT		(1)(21)	(2)	(2)	(2)	(8)(24)
STORAGE	106		○						○						●			9'-4"	EPOXY PAINT		(1)	(2)	(2)	(2)	(8)(9)
CORRIDOR	107	○								○				○	●			9'-4"	EPOXY PAINT		(1)(21)	(2)(3)	(2)(3)	(2)(3)	(10)
MVA	108		○							○					●			9'-4"	EPOXY PAINT		(1)(21)	(2)	(2)	(2)	(8)(24)(25)
MVA	109		○							○					●			9'-4"	EPOXY PAINT		(1)(21)	(2)	(2)	(2)	(8)(24)(25)
LIFE SKILLS	110		○							○					●			9'-4"	EPOXY PAINT		(1)(21)	(2)	(2)	(2)	(8)(24)(25)
CORRIDOR	111	○								○				○	●			10'-8" / 11'-4"			(1)(21)	(2)(3)	(2)(3)	(2)(3)	(10)
KITCHEN	112				○						○						○	10'-0"			(22)	(26)	(26)	(26)	(27)
CORRIDOR	113				○						○						○	10'-0"			(22)	(26)	(26)	(2)	(26)(27)
DRY STORAGE	114				○						○						○	10'-0"			(22)	(26)	(26)	(26)	(27)
DISH	115				○						○						○	10'-0"			(22)	(26)	(26)	(26)	(27)
CUSTODIAN	116				○						○				●			9'-4"	EPOXY PAINT		(1)	(2)	(2)	(2)	(2)	(27)
TOILET	117			○				○							●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
CORRIDOR	118				○						○						○	10'-0"			(21)	(26)	(26)	(26)	(27)
LOCKER ROOM	119			○				○						○	●			9'-4"			(1)	(15)	(15)	(15)	(15)	(14)
OFFICE	120				○						○			○	●			9'-4"			(21)	(2)	(2)	(2)	(2)	(27)
DINING	121					○			○					○	●			9'-6"			(5)(21)	(2)	(2)	(2)	(2)	(9)(16)(25)
MECHANICAL	122						○		○				●		●			----			(5)	(2)	(2)	(2)	(2)	(9)
MECH. / ELEC.	123						○		○				●		●			10'-0"	EPOXY PAINT		(1)	(2)	(2)	(2)	(2)	(9)
CORRIDOR	124					○			○				●		●			9'-0"			(1)	(2)	(2)	(2)	(2)	(9)(16)
TOILET	125			○				○					●					9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	126			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
CORRIDOR	127	○							○				●	○	●			10'-8" / 11'-4"			(1)(21)	(2)(3)	(2)(3)	(2)(3)	(2)(3)	(10)
STAIRS	128	○							○						●			----			----	(2)	(2)	(2)	(2)	(5)(9)(10) RUBBER TREADS & RISERS
EQUIPMENT	129						○		○				●		●			9'-4"	EPOXY PAINT		(1)	(2)	(2)	(2)	(2)	(9)
ELEVATOR	130	○																----			----	----	----	----	----	(10)
MECH. / ELEC.	131						○		○				●		●			----	EPOXY PAINT		(5)	(2)	(2)	(2)	(2)	(9)
CLASSROOOM	132		○						○				●	○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)
CUBBIES	133		○						○				●	○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(25)
CLASSROOM	134		○						○				●	○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(8)(24)(25)
CLASSROOM	135		○						○				●	○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(8)(24)(25)
STORAGE	136						○		○				●		●			----			(5)	(2)	(2)	(2)	(2)	(8)(9)
CORRIDOR	137	○								○			●	○	●			10'-8" / 11'-4"			(1)(21)	(2)(3)	(2)(3)	(2)(3)	(2)(3)	
CLASSROOM	138		○							○			●	○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)(25)
MECH. / FIRE	139						○		○				●		●			----	EPOXY PAINT		(5)	(2)	(2)	(2)	(2)	(9)
STORAGE	140		○						○				●		●			9'-4"			(1)	(2)	(2)	(2)	(2)	(8)(9)
TOILET	141			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
LPC OFFICE	142		○						○			○	●		●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(24)(25)
CUSTODIAN	143					○			○				●		●			9'-4"	EPOXY PAINT		(1)	(2)	(2)	(2)	(2)	(9)
TOILET	144			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	144a			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	144b			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	144c			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	144d			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	144e			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	144f			○				○					●		●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
CONFERENCE	145		○						○				●		●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(25)
COORIDOR	146	○							○				●		●			10'-8" / 11'-4"			(1)(21)	(2)(3)	(2)(3)	(2)(3)	(2)(3)	(10)
COORIDOR	147	○							○				●		●			10'-8" / 11'-4"			(1)(21)	(2)(3)	(2)(3)	(2)(3)	(2)(3)	(10)

SECOND FLOOR

DESCRIPTION	RM. NO.	FLOOR						BASE						CEILING				CLG. HT.	REMARKS	WALLS	PAINT / COLOR SCHEDULE				
		LUXURY VINYL TILE	CARPET TILE	CERAMIC TILE	QUARRY TILE	STAINED CONCRETE	EXPOSED CONCRETE W/ HARDENER	CERAMIC TILE	RUBBER	WOOD	QUARRY TILE	NONE		2 X 2 ACOUT. LAY-IN (TEG)	GYP. BOARD	EXPOSED STRUCTURE	KITCHEN ZONE LAY-IN			CERAMIC TILE / CONCRETE MASONRY UNIT / GYP. BD. / WAINSCOT / STAINLESS STL.	CLG.	N	E	S	W	REMARKS
CLASSROOM	201		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	
CLASSROOM	202		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(23)(24)
TOILET	203				○				○						●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	203a				○				○						●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	203b				○				○						●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	203c				○				○						●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	203d				○				○						●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	203e				○				○						●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
TOILET	203f				○				○						●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
ACO	204		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(25)
STORAGE	205	○								○				○				9'-4"			(21)	(2)	(2)	(2)	(2)	(3)
CORRIDOR	206	○								○				○	●			10'-8" / 11'-4"			(1)(21)	(2)(3)	(2)(3)	(2)(3)	(2)(3)	(10)
ACO	207		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(25)
SMALL GROUP	208		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(25)
BREAK ROOM	209	○								○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(10)(25)
TOILET	210				○				○						●			9'-4"	EPOXY PAINT		(1)	(15)	(15)	(15)	(15)	(14)
PRINCIPAL	211		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(25)
SECRETARY	212		○							○				○	●						(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(17)(18)
ASSIST. PRINCIPAL	213		○							○				○	●						(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(25)
NIGHT PRINCIPAL	214		○							○				○	●						(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(25)
STORAGE	215		○							○				○	●						(1)(21)	(2)	(2)	(2)	(2)	(3)(8)
COPY	216		○							○				○	●						(1)(21)	(2)	(2)	(2)	(2)	(3)(8)
CLASSROOM	217		○							○				○	●						(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)(25)
CORRIDOR	218	○								○				○	●			10'-8" / 11'-4"			(1)(21)	(2)(3)	(2)(3)	(2)(3)	(2)(3)	(10)
NUMBER NOT USED	219																									
CLASSROOM	220		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)(25)
CLASSROOM	221		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)(25)
STAIRS	222	○								○					●			10'-8"			(1)	(2)	(2)	(2)	(2)	(5)(10) RUBBER TREADS & RISERS
ELEVATOR	223	○																								(10)
I.T.	224											○		○				9'-4"			(21)	(2)	(2)	(2)	(2)	(9)
MECH. / ELEC.	225											○				●		----	EPOXY PAINT		(5)	(2)	(2)	(2)	(2)	(9)
CUSTODIAN	226											○			●			9'-4"	EPOXY PAINT		(1)	(2)	(2)	(2)	(2)	(9)
CLASSROOM	227		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)(25)
CLASSROOM	228		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)(25)
CLASSROOM	229		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)(25)
CLASSROOM	230		○							○				○	●			10'-8" / 11'-4"			(1)(21)	(2)	(2)	(2)	(2)	(3)(8)(24)(25)

COORDINATE ALL COLORS & THEIR LOCATIONS, QUANTITIES, ETC. W/ THE ARCHITECT PRIOR TO ACQUIRING MATERIALS

1 ROOM FINISH SCHEDULE

- SCHEDULE ORIENTED SAME AS PLAN
- INDICATES MATERIAL IN A GIVEN AREA
- MATERIAL ON ALL SURFACES
- MATERIAL ON EACH INDIVIDUAL SURFACE
- IF CIRCLE IS BLACKENED - SURFACE TO RECEIVE PAINTER'S FINISH
- IF CIRCLE IS BLANK - SURFACE OR MATERIAL IS PREFINISHED OR NOT PAINTED

GENERAL NOTE:

PROVIDE CONCRETE HARDENER AT ALL CHASE / EXPOSED CONC. LOCATIONS

PAINT:

(1) GYP. BOARD CEILINGS: SHERWIN-WILLIAMS - SW7006 - EXTRA WHITE
(2) WALLS - FIELD: SHERWIN-WILLIAMS - SW7008 - ALABASTER
(3) WOOD WAINSCOTTING & WOOD TRIM / BASE: SHERWIN-WILLIAMS - SW7052
(4) H.M. DOORS & FRAMES : SHERWIN-WILLIAMS - SW6992 - INKWELL
(5) MISCELLANEOUS METALS: SHERWIN-WILLIAMS - SW6992 - INKWELL
(6) WOOD DOORS - CLEAR CL07
(7) EXTERIOR H.M. DOORS & FRAMES & WINDOWS: SHERWIN-WILLIAMS - SW6992 - INKWELL

PREFINISHED COLORS:

(8) CARPET TILES: INTERFACE FLOR - COLOR "A" : 410-107025 NATURAL - COLOR "B": AE317-105829 AZURE
(9) RUBBER WALL BASE: ROPPE - 100 BLACK
(10) LUXURY VINYL TILE COLOR (A) : INTERFACE LVT - STUDIO SET -
(11) LUXURY VINYL TILE COLOR (B) : INTERFACE LVT - STUDIO SET -
(12) GROUT: COLOR 1 TO BE SELECTED FROM MFR'S STANDARD COLORS

2 COLOR SCHEDULE

PREFINISHED COLORS:

(13) GROUT: COLOR 2 TO BE SELECTED FROM MFR'S STANDARD COLORS
(14) CERAMIC TILE FLOORS: DALTILE - SYNCHRONIC - GREY SY33 OR TILEBAR - MARBELLA - GREIGE GRAY
(15) CERAMIC TILE WALLS & BASE: DALTILE - SYNCHRONIC - WHITE SY30 OR TILEBAR - MARBELLA - DESERT SAND BEIGE W/ MTL. TRIM @ ALL OUTSIDE CORNERS
(16) CONCRETE FLOOR STAIN : AMERIPOLISH - ****
(17) SOLID SURFACE (COUNTERTOPS) :CORIAN - ****
(18) PLASTIC LAMINATE (FACING AND EDGING) : WILSONART - 7925-38 - MONTICELLO MAPLE
(19) VINYL "T" EDGING: - TO BE SELECTED FROM MFR'S STANDARD COLORS
(20) MELAMINE: TO BE SELECTED FROM MFR'S STANDARD COLORS
(21) 2 X 2 ACOUSTICAL LAY - IN TILES - TEGULAR EDGE : REFER SPECIFICATIONS
(22) 2 X 2 ACOUSTICAL LAY - IN TILES - KITCHEN ZONE : REFER SPECIFICATIONS
(23) INTERIOR SIGNAGE: MOHAWK SIGN SYSTEMS - BLACK W/ WHITE LETTERS
(24) MARKERBOARD: CLARIDGE - NO. 100 - LCS WHITE
(25) TACKBOARD: CLARIDGE - KB662 - GREY
(26) STAINLESS STEEL WALL PANELS : REFER SPECIFICATIONS REFER PLANS FOR LOCATIONS
(27) QUARRY TILE & BASE :

EXTERIOR COLORS:

(28) MASONRY BRICK VENEER - CLOUD CERAMICS - LIGHT IVORY VELOUR
(29) MASONRY BRICK VENEER - KANAS BRICK AND TILE - 530 FLASH
(30) PREFINISHED METAL SOFFIT PANEL: COLOR TO BE SELECTED FROM ALL MFR. COLORS - BERRIDGE -
(31) PREFINISHED METAL COPING: COLOR TO BE SELECTED FROM ALL MFR. COLORS - MATCH PREFINISHED WALL PANELS
(32) MASONRY MORTAR - COLOR TO BE SELECTED FROM ALL MFR. COLORS

AGP
the Abla Griffin Partnership L.L.C.

313 S. E. 5th Street
MOORE, OK. 73160
405.735.3477
AGP@theAGP.net
www.theAGP.net

CEDAR CREEK
CIVIL

KFC ENGINEERING
STRUCTURAL

SALAS O'BRIEN
MECHANICAL / ELECTRICAL

STATE OF OKLAHOMA
MICHAEL L. ABLA
26139
REGISTERED ARCHITECT
12/1/25

CG
drawn by

MA
checked by

NOVEMBER 2025
date

revisions

MOORE PUBLIC SCHOOLS

OLD SCHOOL REPLACEMENT

sheet no:
A601

ROOM FIN. SCHEDULE

OWNERSHIP USE OF DOCUMENTS:

AGP EXPRESSLY RESERVES ITS COPYRIGHT AND OTHER PROPERTY RIGHTS OF ALL PLANS AND DRAWINGS DESIGNED AND/OR PRODUCED. PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED IN ANY FORM OR MANNER WITHOUT THE EXPRESSED WRITTEN CONSENT OF AGP.