


**FOODSERVICE EQUIPMENT PLUMBING CONNECTIONS PLAN**  
1/4" = 1'-0"



**TROUGH PIPING DETAIL**  
NO SCALE

**PLUMBING CONNECTIONS SCHEDULE**

NO.	ITEM NO.	SIZE	DESCRIPTION	LOCATION	APP.	SERVICE TO	REMARKS
F01	Ø1 1/11	...	FD	FLOOR FLOOR	Ø1	...	AREA DRAIN
F03	12, 18, 23, 24, 4 32	12" SQ.	FL. SINK	FLOOR	Ø1	...	THE PLUMBING CONTRACTOR IS TO FURNISH AND INSTALL THE LINE TO THE PLUMBING CONTRACTOR TO THE FL. SINK FURNISH WITH A 1/2 GRATE
F04	36	Ø1 SQ.	FL. SINK	FLOOR	Ø1	...	THE PLUMBING CONTRACTOR IS TO FURNISH AND INSTALL THE LINE TO THE PLUMBING CONTRACTOR TO THE FL. SINK FURNISH WITH A 1/2 GRATE
F05	12, 18, 23, 24, 31, 35, 37, 4 35	...	W	EQUIP.	...	...	THE PLUMBING CONTRACTOR IS TO FURNISH AND INSTALL THE LINE TO THE PLUMBING CONTRACTOR TO THE FL. SINK FURNISH WITH A 1/2 GRATE
F07	16	1/2"	H 4 CU	FLOOR	3/4"	FAUCET	...
F08	18	1/2"	H 4 CU	FLOOR	3/4"	FAUCET	...
F09	45	2"	H 4 CU	FLOOR	9"	TOP SINK	...
F10	42	1/2"	H 4 CU	FLOOR	9"	WASHER	...
F11	42	1/2"	DR CU	FLOOR	42"	WASHER	...
F12	42, 4 18	2"	H 4 CU	FLOOR	42"	FAUCET	...
F13	47	1/2"	H 4 CU	FLOOR	9"	FAUCET	...
F14	47	1/2"	H 4 CU	FLOOR	9"	FAUCET	...
F15	24	3/4"	H 4 CU	FLOOR	12"	FILL FAUCET 4 SPRAY HEAD	...
F16	36	1/2"	H 4 CU	FLOOR	9"	FILL FAUCET	...
F17	36	1/2"	H 4 CU	FLOOR	9"	COMB. OVEN	...
F18	73	1/2"	W	FLOOR	12"	CONV. OVEN	...
F19	51	1/2"	W	FLOOR	12"	DISHWASHER	...
F20	51	3/4"	W	FLOOR	12"	DISHWASHER	...
F21	47	3/4"	H 4 CU	FLOOR	12"	DISHWASHER	...
F22	49	1/2"	H 4 CU	FLOOR	12"	DISHWASHER	...
F23	49	1/2"	H 4 CU	FLOOR	12"	DISHWASHER	...
F24	25 & 26	...	GAS	FLOOR	18"	...	...

**PLUMBING SYMBOLS**

⊕	HU	HOT WATER
⊖	CU	COLD WATER
⊙	G	GAS SUPPLY
⊚	DR	DRAIN
⊛	W	INDIRECT WASTE (EXTEND TO FD)
⊜	FD	FLOOR DRAIN
⊝	F5	FLOOR SINK - 1/2 GRATE
⊞	F6	FLOOR SINK - FULL GRATE
⊟	AFF	ABOVE FINISHED FLOOR
⊠	FD1	BRANCH FROM ABOVE

**NOTES**

THE PLUMBING CONTRACTOR TO ROUGH-IN FROM THE FOODSERVICE CONTRACTORS ROUGH-IN DRAWINGS ONLY. THE PLUMBING CONTRACTOR WILL TAKE FULL RESPONSIBILITY FOR THE ROUGH-IN LOCATIONS IF THE FOODSERVICE AND/OR PLUMBING DRAWINGS ARE USED FOR THIS WORK.

**PLUMBING/MECHANICAL NOTES**

- DO NOT ROUGH-IN FROM THIS DRAWING. REFER TO CONTRACTOR'S DIMENSIONED DRAWINGS.
- DIMENSIONS INDICATED ARE TO BE VERIFIED BY THE FOODSERVICE CONTRACTOR AND ADJUSTED AS REQUIRED BY THE FOODSERVICE EQUIPMENT OR FIELD CONDITIONS.
- VENTILATE REFRIGERATION MACHINERY ROOMS TO PROVIDE 95°F MAXIMUM AMBIENT TEMPERATURE.
- EXHAUST DUCTS AND FANS CONNECTED TO EXHAUST HOODS SHALL NOT SERVE ANY OTHER AREA OR APPLIANCE.
- DUCTS OF MULTIPLE EXHAUST HOODS WITH COMMON CONTROL PANEL MUST BE INTERLAPPED FOR USE WITH A SINGLE EXHAUST FAN.
- THE FOLLOWING WORK IS BY THE PLUMBING CONTRACTOR. REFER TO THE PLUMBING DRAWINGS AND/OR SPECIFICATIONS FOR ADDITIONAL INFORMATION.
- FIELD INSTALLATION OF ACCESSORIES & FITTINGS PROVIDED LOOSE WITH THE FOODSERVICE EQUIPMENT.
- SERVICE SINKS, LAVATORIES AND DRINKING FOUNTAINS.
- GRAB-BAR EXHAUST DUCTS FROM VENT CONNECTIONS OF THE EXHAUST HOODS.
- FLUSHING-OUT OF ALL PIPING AND DRAINAGE SYSTEMS PRIOR TO CONNECTION TO FOODSERVICE EQUIPMENT.

**AGP**  
the Abba Griffin  
Partnership L.L.C.  
313 S. E. 5th Street  
MOORE, OK 73160  
405.735.3477  
AGP@theAGP.net  
www.theAGP.net

CEADAR CREEK  
CIVIL  
KFC ENGINEERING  
STRUCTURAL  
SALAS OBREN  
MECHANICAL/ELECTRICAL

**MOORE**  
PUBLIC SCHOOLS

OLD SCHOOL  
UPGRADES

Sheet No:  
**FS301**

OWNERSHIP USE OF DOCUMENTS:  
APP EXPRESSLY RESERVES ITS  
COPYRIGHT AND OTHER PROPERTY  
RIGHTS OF ALL PLANS AND DRAWINGS  
DESIGNED AND/OR PRODUCED. PLANS  
AND DRAWINGS ARE NOT TO BE  
REPRODUCED IN ANY FORM OR MANNER  
WITHOUT THE EXPRESS WRITTEN  
CONSENT OF AGP.