



4. PROVIDE WOOD BLOCKING AT ALL WALL MOUNTED ITEMS IN NEW STUD WALLS. RE: 21A901

5. ADD CORNER GUARDS (C.G.) AT ALL INTERIOR LOCATIONS NOTED

NOTE: CONTRACTOR TO VERIFY THAT THE MOUNTING HEIGHTS OF ALL WALL MOUNTED FIXTURES (I.E. PLUMBING FIXTURES, GRAB BARS, MIRRORS, ETC.) MEET ALL APPLICABLE CODES & STANDARDS PRIOR TO INSTALLATION.

- GENERAL NOTES:
1. F.E.C. - FINE EXTINGUISHER AND CABINET
 2. REMOVE EXISTING H.M. FRAME & WID. DOOR AND PREPARE OPENING TO RECEIVE NEW STUD IN FILL WITH GYP. BD EACH SIDE MATCH EXISTING WALL THICKNESS COORDINATE WITH ARCHITECT. PAINT ENTIRE WALL AT EXISTING CORRIDOR SIDE. RE: ROOM FINISH SCHEDULE
 3. REMOVE EXISTING H.M. DOOR & FRAME AND PREPARE OPENING TO RECEIVE NEW STUD IN FILL WITH GYP. BD & BRICK VENERER MATCH EXISTING WALL THICKNESS COORDINATE WITH ARCHITECT

