



NOTES BY SYMBOL - SHEET M202

NUMBER	DESCRIPTION
1	EXISTING ROOFTOP UNITS TO REMAIN. ENSURE EQUIPMENT IS IN PROPER WORKING ORDER AND SERVICE AS REQUIRED. REFER TO EXISTING MECHANICAL EQUIPMENT NOTES ON M400 FOR FURTHER INFORMATION. COORDINATE THERMOSTAT LOCATION AND MOUNTING HEIGHT IN FIELD AND WITH ARCHITECTURAL DRAWINGS PRIOR TO BID. REBALANCE OUTSIDE AIR AND EXHAUST AIR TO VALUES SHOWN IN AIR BALANCE SCHEDULES. VERIFY PRESENCE OF DUCT SMOKE DETECTORS. PROVIDE IF ABSENT. SMOKE DETECTORS SHALL BE WIRED TO SHUT DOWN RTU'S IN THE EVENT OF SMOKE IS DETECTED. PROVIDE HAIL GUARD ON ALL UNITS.
2	PROVIDE ROOF-MOUNTED EXHAUST FANS PER SCHEDULE. PROVIDE ALL NECESSARY SUPPORTS, ACCESSORIES, AND APPURTENANCES REQUIRED FOR A COMPLETE INSTALLATION AND INSTALL PER MANUFACTURERS RECOMMENDATIONS. COORDINATE EXACT LOCATIN IN FIELD PRIOR TO BID. G.C. TO CUT AND PATCH ROOF AS REQUIRED. SEAL ALL PENETRATIONS AIR AND WATER TIGHT. REFER TO DETAIL ON SHEET M300 FOR FURTHER INFORMATION. MAINTAIN ALL CODE REQUIRED CLEARANCES, INCLUDING MINIMUM OF 10'-0" CLEARANCE FROM ALL OUTSIDE AIR INTAKES.
3	DASHED LINES INDICATING 10'-0" CLEARANCE FROM ALL OUTSIDE AIR INTAKES.
4	PROVIDE PRIMEXVENTS RC-26 ROOF CAP. EXHAUST DUCT TO BE VENTED TO ROOF ABOVE. REFER TO DETAIL 12 (DRYER VENT DETAIL) ON SHEET M300 FOR MORE INFORMATION.

