DESCRIPTION	RM. NO.	FLOOR						BASE					CEILING					CLG. HT.	REMARKS	RM. NO.	WALLS						PAINT / COLOR SCHEDULE				
		NOT USED	CARPET TILE	CERAMIC TILE	TERRAZZO TILE	EXPOSED CONCRETE W/ HARDENER		CERAMIC TILE	RUBBER	TERRAZZO TILE	NONE		2 X 2 ACOUST. LAY-IN (TEG)	NOT USED	GYP. BOARD	EXPOSED STRUCTURE				CERAMIC TILE	CONCRETE MASONRY UNIT	EXISTING WALL	GYP. BD.	EXPOSED CONCRETE	CERAMIC WALL PANELS	CLG.	WALLS N	WALLS E	WALLS S	WALLS W	REMARKS
VESTIBULE	1				○				○						●			24'-0"		1					▨	▨	(5)(24)	–	(20)	–	(20)	(10)(17)
CONCOURSE	2				○				○				○		●			24'-0"		2					▨	▨	(5)(24)	(20)	(20)	–	(20)	(10)(17)
LOBBY	3				○				○				○					12'-0"		3		●					(1)(24)	(2)	(2)	(2)	(2)	(10)(17)(18)(19)
SECRETARY	4		○					○					○					10'-0"		4		●					(24)	(3)	(2)	(2)	(2)	(8)(9)(23)
SECRETARY	5		○					○					○					10'-0"		5		●					(24)	(3)	(2)	(2)	(2)	(8)(9)(23)
SECRETARY	6		○					○					○					10'-0"		6		●					(24)	(3)	(2)	(2)	(2)	(8)(9)(23)
SECRETARY	7		○					○					○					10'-0"		7		●					(24)	(3)	(2)	(2)	(2)	(8)(9)(23)
CORRIDOR	8				○					○					●			10'-0"		8		●					(1)	(2)	(–)	(2)	(–)	(10)(17)
CONFERENCE	9		○					○					○		●			10'-0"		9		●					(1)(24)	(2)	(3)	(2)	(2)	(8)(9)(23)
SECURITY	10		○					○					○					9'-4"		10		●					(24)	(2)	(2)	(2)	(2)	(8)(9)(23)
CORRIDOR	11				○					○			○		●			10'-0"		11		●					(1)(24)	(2)	(2)	(2)	(2)	(10)(17)
OFFICE	12		○					○					○					9'-4"		12		●					(24)	(3)	(2)	(2)	(2)	(8)(9)(23)
OFFICE	13		○					○					○					9'-4"		13		●					(24)	(3)	(2)	(2)	(2)	(8)(9)(23)
OFFICE	14		○					○					○					9'-4"		14		●					(24)	(2)	(2)	(3)	(2)	(8)(9)(23)
OFFICE	15		○					○					○					9'-4"		15		●					(24)	(3)	(2)	(2)	(2)	(8)(9)(23)
OFFICE	16		○					○					○					9'-4"		16		●					(24)	(2)	(2)	(3)	(2)	(8)(9)(23)
COPY	17				○					○			○		●			9'-4"		17		▪					(1)(24)	(2)	(–)	(2)	(2)	(10)(17)
CORRIDOR	18				○					○					●			10'-0"		18		▪					(1)	(2)	(–)	(2)	(–)	(10)(17)
PRINCIPAL SECRETARY	19		○					○					○					9'-4"		19		▪					(24)	(2)	(2)	(3)	(2)	(8)(9)(23)
PRINCIPAL OFFICE	20		○					○					○					9'-4"		20		●					(24)	(2)	(2)	(2)	(3)	(8)(9)(18)(19)(23)
RECEPTION	21				○					○			○		●			8'-8" / 10'-0"		21		▪					(1)(24)	(2)	(2)	(2)	(2)	(10)(17)(18)(19)(23)
CORRIDOR	22				○					○			○		●			10'-0"		22		●					(1)(24)	(2)	(2)	(2)	(2)	(10)(17)
MEN	23			○				○							●			9'-4"	EPOXY PAINT	23	⊠						(1)	(15)	(15)	(15)	(15)	(14)(26)
WOMEN	24			○				○							●			9'-4"	EPOXY PAINT	24	⊠						(1)	(15)	(15)	(15)	(15)	(14)(26)
BREAK ROOM	25				○					○			○					9'-4"		25		●					(24)	(3)	(2)	(2)	(2)	(10)(17)(18)(19)(23)
MECH. / ELEC.	26					○		○								●		---	EPOXY PAINT	26		●					(1)	(2)	(2)	(2)	(2)	(9) EPOXY PAINT
STORAGE	27				○					○			○					10'-0"		27		●					(24)	(2)	(2)	(2)	(2)	(10)(17)
CUSTODIAN	28					○		○							●			9'-4"	EPOXY PAINT	28		●					(1)	(2)	(2)	(2)	(2)	(9) EPOXY PAINT
VESTIBULE	29				○					○					●			9'-4"		29		●					(1)	(2)	(2)	(2)	(2)	(10)(17)
ATHLETIC FACILITATOR	30		○					○					○					9'-4"		30		●					(24)	(2)	(2)	(2)	(3)	(8)(9)(23)
ATHLETIC SECRETARY	31		○					○					○					9'-4"		31		●					(24)	(2)	(2)	(2)	(3)	(8)(9)(23)
FINANICAL SECRETARY	32		○					○					○					9'-4"		32		●					(24)	(2)	(3)	(2)	(2)	(8)(9)(23)
I.T.	33					○		○							●			9'-4"		33		●					(1)	(2)	(2)	(2)	(2)	(9)
SECURITY	34		○					○					○					9'-4"		34		●					(24)	(2)	(3)	(2)	(2)	(8)(9)(23)
DINING ROOM	35				○					○			○		●			10'-0" / 12'-0"		35		▪					(1)(24)	(2)	(2)	(2)	(2)	(10)(17)
CORRIDOR	36				○					○					●			10'-0"		36		▪	○				(1)	(2)	(2)	(2)	(2)	(10)(17)
EXISTING OFFICE	E1		○					○					○					8'-8"		E1		●					(24)	(2)	(2)	(2)	(2)	(8)(9)
EXISTING OFFICE	E2		○					○					○					8'-8"		E2		●					(24)	(2)	(2)	(2)	(2)	(8)(9)
EXISTING OFFICE	E3		○					○					○					8'-8"		E3		●					(24)	(2)	(2)	(2)	(2)	(8)(9)
EXISTING OFFICE	E4		○					○					○					8'-8"		E4		●					(24)	(2)	(2)	(2)	(2)	(8)(9)

GENERAL NOTE:

PROVIDE CONCRETE HARDENER AT ALL CHASE LOCATIONS

1 ROOM FINISH SCHEDULE

- ▨ SCHEDULE ORIENTED SAME AS PLAN
- ◯ INDICATES MATERIAL IN A GIVEN AREA
- ▨ MATERIAL ON ALL SURFACES
- ▨ MATERIAL ON EACH INDIVIDUAL SURFACE
- ● IF CIRCLE IS BLACKENED - SURFACE TO RECEIVE PAINTER'S FINISH
- ○ IF CIRCLE IS BLANK - SURFACE OR MATERIAL IS PREFINISHED OR NOT PAINTED

PAINT:

1. GYP. BOARD CEILINGS / EXPOSED STRUCTURE: SHERWIN-WILLIAMS - SW7006 - EXTRA WHITE
2. WALLS - FIELD: SHERWIN-WILLIAMS - SW7008 - ALABASTER
3. WALL - ACCENT WALL: SHERWIN-WILLIAMS - SW7016 MINDFUL GRAY
4. H.M. DOORS & FRAMES : SHERWIN-WILLIAMS - SW6992 - INKWELL
5. MISCELLANEOUS METALS - INCLUDING STAIR STRUCTURE, HANDRAILS, EXPOSED ANGLES THAT ARE NOT GALVANIZED, ETC.: SHERWIN-WILLIAMS - SW6992 - INKWELL
6. WOOD DOORS : - CLEAR CL07
7. NUMBER NOT USED

PREFINISHED COLORS:

8. CARPET TILES: COLOR "A": INTERFACE- OPEN AIR 410-106970 NATURAL COLOR "B": INTERFACE - LUMINESCENT - NIGHT LIGHTS - 107236 IRON POPPY
9. RUBBER WALL BASE: ROPPE - 100 BLACK
10. TERRAZZO TILE WALL BASE: FLOORAZZO GEM COLLECTION - ESPRESSO MACCHIATO
11. NUMBER NOT USED
12. GROUT: COLOR 1 TO BE SELECTED FROM MFR'S STANDARD COLORS
13. GROUT: COLOR 2 TO BE SELECTED FROM MFR'S STANDARD COLORS
14. CERAMIC TILE FLOORS: AMERICAN OLEAN - ULTRA MODERN - UM07 - PROGRESSIVE GRAY OR CROSSVILLE ROCA STRATOS ORION NEGRO / ANTRACITA
15. CERAMIC TILE WALLS & BASE: AMERICAN OLEAN - ULTRA MODERN - UM05 - INFINITE CREAM OR CROSSVILLE ROCA STRATOS ORION BLANCO W/ MTL. TRIM @ ALL OUTSIDE CORNERS
16. NUMBER NOT USED
17. TERRAZZO TILE: FLOORAZZO COLOR "A" - GEM COLLECTION - PERAL COLOR "B" - GEM COLLECTION - ESPRESSO MACCHIATO COLOR "C" - GEM COLLECTION - CUSTOM COLOR
18. SOLID SURFACE (COUNTERTOPS, WINDOW SILLS & TRIM) :CORIAN - DEEP BLACK QUARTZ
19. PLASTIC LAMINATE (FACING AND EDGING) : WILSONART - D315-60 PLATINUM
20. CERAMIC WALL PANELS: COLOR "A" CROSSVILLE - FOKOS 5.6 - SALE L3914 COLOR "B" CROSSVILLE - FOKOS 5.6 - ROCCIA - L3916
21. VINYL "T" EDGING: - TO BE SELECTED FROM MFR'S STANDARD COLORS
22. MELAMINE: TO BE SELECTED FROM MFR'S STANDARD COLORS
23. TACKBOARD: BEST-RITE CHALKBOARD CO. -BR-015 - ANTIQUE WHITE
24. 2 X 2 ACOUSTICAL LAY - IN TILES - TEGULAR EDGE : REFER SPECIFICATIONS
25. INTERIOR SIGNAGE: MOHAWK SIGN SYSTEMS - BLACK W/ WHITE LETTERS
26. TOILET PARTITIONS : BRADLEY - STAINLESS STEEL
27. NUMBER NOT USED
28. NUMBER NOT USED

EXTERIOR COLORS:

29. PREFINISHED METAL CANOPY : MAPES - REGAL RED
30. MASONRY BRICK VENEER - TO BE VERIFIED WITH ARCHITECT PRIOR TO CONSTRUCTION -ACME - WEATHERWOOD GRAY
31. MASONRY BRICK VENEER - TO BE VERIFIED WITH ARCHITECT PRIOR TO CONSTRUCTION - ACME - CHARCOAL GRAY
32. PREFINISHED METAL SOFFIT PANEL: COLOR TO BE SELECTED FROM MFR. STANDARD COLORS - BERRIDGE - MATTE BLACK
33. PREFINISHED METAL COPING, WALL PANELS, GUTTERS & DOWNSPOUTS: BERRIDGE - MATT BLACK
34. NUMBER NOT USED
35. MASONRY MORTAR - TO BE VERIFIED WITH ARCHITECT PRIOR TO CONSTRUCTION - MATCH EXISTING - SPEC MIX SM

2 COLOR SCHEDULE

AGP
the Abla Griffin Partnership L.L.C.

313 S. E. 5th Street
MOORE, OK. 73160
405.735.3477
AGP@theAGP.net
www.theAGP.net

CEDAR CREEK
CIVIL

KFC ENGINEERING
STRUCTURAL

SALAS O'BRIEN
MECHANICAL / ELECTRICAL

STATE OF OKLAHOMA
MICHAEL L. ABLA
2639
OKLAHOMA CITY, OKLAHOMA
REGISTERED ARCHITECT
3/2/26

CG
drawn by

MA
checked by

AUGUST 2025
date

revisions

MOORE PUBLIC SCHOOLS

WESTMOORE HIGH SCHOOL ENTRY UPGRADES

sheet no:
A601

ROOM FIN. SCHEDULE

OWNERSHIP USE OF DOCUMENTS:

AGP EXPRESSLY RESERVES ITS COPYRIGHT AND OTHER PROPERTY RIGHTS OF ALL PLANS AND DRAWINGS DESIGNED AND/OR PRODUCED. PLANS AND DRAWINGS ARE NOT TO BE REPRODUCED IN ANY FORM OR MANNER WITHOUT THE EXPRESSED WRITTEN CONSENT OF AGP.